1483 - 5 OF 5

A. General

1. Operations shall proceed in accordance with the AMP which is comprised of Drawing 5 of these site plan notes, as updated and approved in accordance with Section F.
2. This AMP immediately is comprised of Section D – Field Sampling Event Parameters and Section C – Continuous Monitoring as updated and approved in accordance with Section F.
3. Monitoring as identified within the AMP and including biological monitoring, will occur for a minimum of three consecutive years prior to commencing extraction below the water table.
4. Should extraction below the water table not occur in year five, subject to approval by MNR, a reduced monitoring program consisting of continuous monitoring in accordance with Table 2 shall be conducted. No other components of the AMP monitoring program are required as part of the reduced monitoring program.
5. If an isolation below the water table occurs for one full year, the reduced monitoring program in Note A.5 is the only monitoring required.
6. All monitoring may be discontinued one year after final extraction is complete, subject to approval by the MNR.

B. Field Sampling Event Parameters

1. Three Paired Monitoring Stations, each composed of a shallow pond and shallow water monitoring location, have been established in the vicinity of the continuous monitoring station at SW4.
2. Pond, creek, and shallow water monitoring locations in the 3 Paired Monitoring Stations shall be monitored as required.
3. In Table 1 below, a monitoring frequency of 16 times per year means once during spring freshet/runoff, each season and once during fall.
4. Monitoring of the reference reach of Walkers Creek shall only be required if the NVCA determines access to the reference reach in a timely manner for the proposed sampling event. If access is not provided, SW1 and SW2 will be used.
5. Benthic biomonitoring activity, described in Table 1 shall consist of kick-pass electrofishing in 50m reaches in order to acquire data on fish species presence, and timed hand picking on periphyton, including relative abundance and length.
6. Three replicate benthic samples, as described in Table 1 shall be collected with a DFO ion Sweep sampler. Such samples will be processed to lowest practical taxa. Data will be analyzed for parameters including richness, density, diversity, evenness and EPT (Ephemeroptera-Plecoptera-Trichoptera).
7. Redd surveys will be conducted following *Salmonid Spawning Surveys of Selected Streams in the Credit River Watershed 1998-1999*, (LA Grillmayer and RJ Baldwin, GRCA).
8. Qualitative aquatic habitat assessment described in Table 1 shall consist of stream characteristics including bank conditions, riparian vegetation and cover, substrate characteristics (including prevalence of fine sediment), instream cover, pointers and flow conditions.

Table 1: Field Sampling (Subject to Sections A and B)

Monitoring Activity	Groundwater Location	Frequency	Surface Water / Side Creek Location	Parameter	Pit Pond Location	Frequency
Water levels	3 boreholes each at the vicinity of BH5-04/2005, and BH5/00-10, and 2 bedrock piezometers at SW4 and SW5, (full suite, manual/electronic) enclosed in constant temperature housing(s), at two weekly intervals for duration of Phase(s) to be confirmed adjacent to B-43001.5, and one shallow (<5m) to be located generally southwest of BH5/00-3	16 times per year	PW1, PW2, PW3	Data to be one year old when on Program to operate for duration of the extraction and rehabilitation activities	permanent staff gauge (to be) placed	At least once per week And Daily during dry periods (when a recorder has not been installed)
Stream Flow	N/A	N/A	at SW4 & SW5 (SW1, SW2, SW3 if required to support the Chloride trigger)	4 times per year at completion of regular monitoring to support the Chloride trigger	N/A	N/A
Temperature	3 boreholes each at the vicinity of BH5-04/2005, and BH5/00-10 and 2 nested piezometers at SW4 and SW5, including completion of excavation footprint piezometer nested pair at 2 nos. Downgradient monitoring well (<5m) to be located generally southwest of BH5/00-3 and one shallow (<5m) to be located generally southwest of BH5/00-5	4 times per year	Spot temperatures at SW1, SW2, SW3, PW1, PW2, PW3 and the Side Streams	4 times per year at completion of regular monitoring to support the Chloride trigger	at staff gauge	Continuous per year
Chloride (MNR trigger, 1st toxic point of chemistry)	3 boreholes each at the vicinity of BH5-04/2005, and BH5/00-10 and 2 nested piezometers at SW4 and SW5, following completion of excavation footprint to near-bedrock monitoring well (2 nos. downgradient monitors, 1 shallow (<5m) to be located adjacent to B-43001.5, and 1 shallow (<5m) to be located generally southwest of BH5/00-5	4 times per year	SW1 and SW2	4 times per year	at staff gauge	once per year
Stream Natural Assessment	N/A	N/A	Quantitative habitat assessment (at/near PW1, PW2, PW3 and in the Side Streams)	once per year	N/A	
Aquatic Benthic Invertebrates	N/A	N/A	At/near stations at PW1, PW2, PW3	once per year during fall		
Aquatic Fish Survey	N/A	N/A	At/near stations at PW1, PW2, PW3 (Note 6) (Credit Watershed Council to provide)	once per year during fall		
Aquatic Redd Survey	N/A	N/A	Upstream and downstream of PW1, PW2, PW3	once per year during fall		

C. Continuous Monitoring (subject to Sections A and C)

1. Continuous monitoring stations for water level and water temperature will be established at boreholes located within the footprint of active water excavation (excavation footprint to operate for monitoring) and downgradient (downgradient monitoring), in-stream measurements, surface water at stations SW1 and SW2 and Pit Pond as per Table 2.
2. "Continuous" monitoring in Table 2 means monitoring between April 1 and October 15 using automated sampling/recording device (data loggers) recording measurements at 0.25 hr intervals.
3. At any location where seasonal or weekly data downloading is required, non-automated sampling/recording device that remotely collects data may be used in which case the seasonal or weekly downloading of data is not required.

Table 2: On-Site Monitoring

Monitoring Activity	Groundwater Location	Frequency	Surface Water / Side Creek Location	Frequency	Pit Pond Location	Frequency
Groundwater	The 6 wells at the vicinity of BH5-04/2005 and BH5/00-10 and 2 nested piezometers at SW4 and SW5, (full suite, manual/electronic) enclosed in constant temperature housing(s), at two weekly intervals for duration of Phase(s) to be confirmed adjacent to B-43001.5, and one shallow (<5m) to be located generally southwest of BH5/00-5	monitoring/reporting with development	Continuous at SW4 & SW5 (and PW1 & PW2)	continuous data logging	permanent staff gauge (to be placed)	continuous monitoring with development; seasonal reporting
Surface Water	2 nested piezometers at the vicinity of BH12/00-5 and BH12/00-6 (one shallow and one deep)	Monitoring and sampling as per Section B	Continuous at SW1, SW2, SW3	Continuous monitoring with field reports	Monthly	Seasonal reporting with annual summary
Benthic Biomonitoring						

D. Data Assessment During Below Water Operations

1. In a season where there is active below water table extraction, the continuous monitoring data collected in accordance with Table 2 will be reviewed weekly (including use of direct downloads and uploads) by the monitoring professionals to determine if trigger have been exceeded.
2. A "monitoring Professional" is a person or persons qualified to interpret monitoring data and provide expert opinion on this adaptive management program including implementation of contingency measures and modifications to monitoring.
3. The field data collected in accordance with Section B shall be compared and assessed with the continuous monitoring data collected in accordance with Section C.

E. Contingency Implementation

1. If the assessment confirms that triggers have been exceeded, and that contingency measures are required, the monitoring professional will notify the site manager of same and implement operational contingencies as per Table 3. MNR and NVCA staff will be advised of a trigger being exceeded.
2. Monitoring professionals will assess the site conditions including more intensive field monitoring as appropriate, and determine when and if contingency measures should be adjusted or discontinued. Contingency measures may be discontinued, after a minimum of 3 days have elapsed, should a trigger not be exceeded.
3. Table 3 identifies initial triggers for implementation of contingency measures in response to monitoring results for water levels. Shallow water monitoring stations, triggers and associated contingency measures will be developed from empirical data in accordance with Note F.1.
4. Additional triggers/variables for flow and downstream temperature and associated contingency measures may be developed in accordance with Note F.5.

Table 3: Pit Pond Contingency Triggers

Pool Depth	Location in the Area of Below Water Extraction	Maximum Weekly Average Temperature (Mon-Sun)
>10 m ►	On the bottom	◄ 15°C
10-15 m ►	25% (1 Target was exceeded)	◄ 18 – 19°C
5-10 m ►	50% (2 Targets were exceeded)	◄ 19 – 20°C
<5 m ►	100% (3 targets exceeded)	◄ >20°C

F. Annual Reporting and AMP Updating

1. A copy of all monitoring data collected in accordance with Section B and Section C will be maintained on-site where it will be available to agency staff upon pre-arranged site meeting basis.
2. An Annual Report prepared by a Monitoring Professional will be submitted to the MNR within 2 months of the end of each calendar year. The MOE and the NVCA will be provided copies of the Annual Report. The Annual Report will contain:
   a) The verified monitoring data collected
   b) An analysis and assessment of the data, and
   c) Recommendations pertaining to:
      i. The suitability of the proposed limit of below water table extraction;
      ii. The rate of aggregate extraction;
      iii. Proposed changes to monitoring, if any;
      iv. Proposed changes to the trigger variables or trigger values and associated contingency measures, if any, and
      v. Proposed operational changes, if any.
3. Prior to implementing any proposed changes contained in an Annual Report, such changes shall be approved by MNR, in consultation with NVCA.
4. Within two weeks of the MNR approval any changes to AMP that are recommended in an Annual Report, an updated Drawing 5 considering as approved changes to the AMP will be prepared and provided to the MNR and copies to the NVCA.
5. Prior to commencing below water table extraction:
   a) Trigger values will be developed for the shallow water monitoring stations and associated contingency measures, based on empirical data from testing regression and other analyses) to the satisfaction of the MNR in consultation with the NVCA and the MOE.
   b) Flow and downstream temperature variables and associated contingency measures will be assessed (including regression and other analyses) for potential new trigger variables and associated contingency measures in the satisfaction of the MNR in consultation with the NVCA and the MOE.
6. Extraction footprint temperature monitoring will be conducted for a period of at least two years following commencement of below water extraction. Assessment of this complete data set will be conducted to confirm model predictions of groundwater temperature events and identify locations for the two additional monitors to be installed (one after downgradient of the extraction limit for below water excavation. This assessment to be included in the Annual Monitoring Report for the year in which it concludes).

G. SHARING OF DATA

1. The NVCA will be provided online access to non-verified monitoring data from Section C – Continuous Monitoring. Verified monitoring data will be included in the Annual Report required by Section F.
2. Data sharing in accordance with Note G.1 shall not be required until the Licensee has entered into a data sharing agreement with the NVCA that preserves the confidentiality of the data shared pursuant to Note G.1, while authorizing that data to be used by the NVCA for monitoring the pit and watershed management.

PART OF LOT 23, CONCESSION 7
EAST OF HURONTARIO STREET
TOWNSHIP OF MULMUR
COUNTY OF DUFFERIN

0 60 120 240 metres
SCALE 1:4000



DECLARATION OF PURPOSE
THIS SITE PLAN IS PREPARED UNDER THE AGGREGATE RESOURCES ACT FOR A CLASS "A" LICENCE, CATEGORY 1.

KEY MAP
N.T.S.



LEGEND

- LICENCED BOUNDARY
- LIMIT OF EXTRACTION ABOVE THE WATER TABLE
- LIMIT OF EXTRACTION BELOW THE WATER TABLE
- LINE INDICATING ALL POINTS WITHIN 120m (MINIMUM) OF LICENCED BOUNDARY
- PROPERTY LINE
- POST & PAGE WIRE FENCE (UNLESS OTHERWISE NOTED)
- PUBLIC ROAD
- WATER COURSE
- CONTOURS
- WOODED AREAS / PLANTATION
- POND
- PIR 3 — PAIRED MONITORING STATION
- BH 2006-10 — GROUNDWATER MONITORING WELL
- PROPOSED MONITORING WELL
- PROPOSED DEEP MONITORING WELL
- SW-7 — SURFACE WATER MONITORING STATION
- SW-T-07 — IN-STREAM PIEZOMETER
- EXCAVATION FOOTPRINT TEMPERATURE MONITORING WELL

SCHEDULE OF AMENDMENTS

NO	DATE	DESCRIPTION	APPROVED
1	July 2014	ADDITIONAL TECHNICAL AND COMPLIANCE REVISIONS	MTG

ANNE TERRY GUIOT
IS APPROVED BY THE MINISTRY OF NATURAL RESOURCES PURSUANT TO SECTION 8 (4) OF THE AGGREGATE RESOURCES ACT TO PREPARE AND CERTIFY SITE PLANS

ANNE TERRY GUIOT — DATE

ARBOUR FARMS PIT
MULMUR TOWNSHIP

LICENSEE: ARBOUR FARMS LTD. c/o ADAM KREHM
245 CARLAW AVENUE, SUITE 107
TORONTO, ONTARIO
M4M 2S8
(416) 466-2042

ADAPTIVE MANAGEMENT PROGRAM

PROJECT NO. 98 - 1483		DRWG. NO. 1483 - 5 OF 5	
DATE: DECEMBER 2012		SCALE: 1:XXX	
DRAWN: CAP	CHECKED: MP	APPROVED: MTG	

Skelton Brumwell & Associates Inc.
ENGINEERING PLANNING ENVIRONMENTAL CONSULTANTS

Copyright: Skelton Brumwell & Associates Inc. All rights reserved. Design and information contained herein, and all rights in copyright, are and shall remain the property of Skelton Brumwell & Associates Inc. and may not be used, except with the written permission of Skelton Brumwell & Associates Inc.